

Rolling Knolls Landfill Superfund SITE
FIELD CHANGE REQUEST (FCR) FORM

Contract No.:

REQUEST NO: 02

DATE: 12/11/2014 (Revised 12/19/2014)
(Revised 12/22/2014)

FCR TITLE: Soil Sample Location Modification

DESCRIPTION:

The Data Gaps Sampling and Analysis Plan (Data Gaps SAP) proposed collection of soil samples at 34 locations (sample locations SS-125 through SS-158). The objective of these soil samples was to further delineate the extent of site constituents at concentrations above the New Jersey Soil Remediation Standards (SRSs) in native soil adjacent to the landfill. Soil sampling locations SS-125 through SS-158 were proposed in native soil near previous soil samples on the landfill where the concentrations of one or more constituents exceeded its SRS.

The Data Gaps SAP indicated sampling at locations SS-125 through SS-158 will be conducted in a step-out manner. Soil samples were proposed in two lines: an inner line approximately 25 feet from the estimated landfill boundary and an outer line approximately 50 feet from the estimated landfill boundary. The estimated landfill boundary presented in the Data Gaps SAP was based on information collected during previous sampling activities. The approximate location of the edge of the estimated landfill boundary is shown in pink in Figure 2 of the Data Gaps SAP. The Data Gaps SAP indicated the landfill boundary will be confirmed based on visual observations at the time of sampling, and that final sample locations may be adjusted if field observations indicate the location of the landfill boundary differs from that shown in Figure 2.

REASON FOR DEVIATION:

Prior to sample collection, visual observations at or near the proposed sample locations indicate the location of the landfill boundary shown in Figure 2 of the Data Gaps SAP should be adjusted, and so the corresponding proposed soil sample locations should also be adjusted. The visual observations included observations of trash or debris at the ground surface. At locations SS-137, SS-138, SS-139, and SS-140, visual observations of trash were observed outside of the original landfill boundary; as a result, samples were moved outward. At locations SS-143, SS-144, SS-145, SS-146, SS-147, SS-148, SS-149, SS-150, SS-157, and SS-158, no visual observations of trash were observed at the original proposed landfill boundary; as a result, samples were moved inward. The approximate distance each sample is moved is included in Table 1.

RECOMMENDED MODIFICATION:

Soil sample locations SS-137, SS-139, SS-143, SS-145, SS-147, SS-149, and SS-157 should be modified to be 25 ft from the landfill boundary as observed in the field rather than the estimated edge of the landfill boundary presented on Figure 2 of the Data Gap SAP. Soil sample locations SS-138, SS-140, SS-144, SS-146, SS-148, SS-150, and SS-158 should be modified to be 50 ft from the landfill boundary as observed in the field rather than the estimated edge of the landfill boundary presented in Figure 2 of the Data Gap SAP. A figure with the revised landfill boundary and the revised sample locations and a table summarizing the revisions is attached to this FCR form.

This figure also shows the locations of test pits excavated during site characterization activities in 2007 and 2008, and indicates where landfilled waste was observed in test pits. The original landfill boundary was developed using visual observations and information from the test pits. The revised landfill boundary includes this same information and refines portions of the boundary using additional visual observations made during implementation of the Data Gaps SAP. The original landfill boundary and the revised landfill boundary both show that all test pits where waste was observed are at or inside the boundary.

Rolling Knolls Landfill Superfund SITE
FIELD CHANGE REQUEST (FCR) FORM

Contract No.:

IMPACT ON PROJECT OBJECTIVES:

The revised sample locations meet the project objective of collecting soil samples in native soil within 25 ft and 50 ft of the landfill boundary to further delineate the extent of site constituents at concentrations above the New Jersey SRSs.

Dated Signatures:  12/22/2014
(Field Team Leader)

 12/22/2014
(Project Manager)



Distribution:

T. Mitchell, EPA Remedial Project Manager
Quality Assurance Coordinator

RI Task Leader
Project File

Table 1
Revised Sample Locations
 Field Change Request (FCR) Form #02
 Rolling Knolls Landfill Superfund Site
 Chatham, New Jersey

Location	Approximate Distance Moved	Basis for Relocation
Landfill boundary at SS-137	15.3 ft	Visual observation of trash outside original landfill boundary; samples were moved outward.
SS-137	11.0 ft	
SS-138	10.5 ft	
Landfill boundary at SS-139	25.2 ft	Visual observation of trash outside original landfill boundary; samples were moved outward.
SS-139	34.9 ft	
SS-140	34.4 ft	
Landfill boundary at SS-143	117.5 ft	Trash was not observed at the original proposed landfill boundary; samples were moved inward.
SS-143	115.0 ft	
SS-144	113.0 ft	
Landfill boundary at SS-145	24.1 ft	Trash was not observed at the original proposed landfill boundary; samples were moved inward.
SS-145	23.3 ft	
SS-146	24.2 ft	
Landfill boundary at SS-147	11.4 ft	Trash was not observed at the original proposed landfill boundary; samples were moved inward.
SS-147	6.3 ft	
SS-148	0.1 ft	
Landfill boundary at SS-149	15.3 ft	Trash was not observed at the original proposed landfill boundary; samples were moved inward.
SS-149	23.5 ft	
SS-150	31.6 ft	
Landfill boundary at SS-157	95.8 ft	Trash was not observed at the original proposed landfill boundary; samples were moved inward.
SS-157	119.6 ft	
SS-158	70.7 ft	



LEGEND:

- OPEN WATER
- EDGE OF LANDFILLED WASTES OBSERVED DURING TEST PIT ACTIVITIES (DASHED WHERE APPROXIMATE)
- GREAT SWAMP NATIONAL WILDLIFE REFUGE PROPERTY BOUNDARY (DASHED WHERE APPROXIMATE)
- REVISED LANDFILL BOUNDARY AND OR WASTE AND DEBRIS OBSERVED ON GROUND SURFACE
- WASTE AND DEBRIS OBSERVED ON GROUND SURFACE BUT NOT OBSERVED OR ANTICIPATED TO BE BELOW GROUND SURFACE
- AREAS WHERE SURFACE WATER FLOW DOES NOT EXHIBIT TYPICAL BED AND BANK MORPHOLOGY
- REVISED WASTE AND DEBRIS OBSERVED ON GROUND SURFACE BUT NOT OBSERVED OR ANTICIPATED TO BE BELOW GROUND SURFACE
- SOIL SAMPLING LOCATION
- SOIL SAMPLING LOCATION WITH DETECTED CONCENTRATIONS GREATER THAN NJDEP NONRESIDENTIAL SOIL REMEDIATION STANDARDS
- PROPOSED MONITORING WELL
- EXISTING MONITORING WELL
- PROPOSED TEMPORARY WELL POINT
- PROPOSED SOIL SAMPLE (PREVIOUS LOCATIONS SHOWN IN GREY)
- REVISED SOIL SAMPLE LOCATION
- PROPOSED SURFACE WATER AND SEDIMENT SAMPLE
- EXISTING SURFACE GAUGE
- COMPLETED TEST PIT LOCATION
- TEST PIT LOCATION WITH LANDFILLED WASTES
- TEST PIT LOCATION WITHOUT LANDFILLED WASTES
- DEPTH OF LANDFILLED WASTES

Nonresidential Soil Remediation Standards

Constituent	Value
VOCs	
Carbon Tetrachloride	2
Chloroform	2
SVOCs	
Acephenone	5
Benzo(a)anthracene	2
Benzo(a)pyrene	0.2
Benzo(b)fluoranthene	2
Benzo(k)fluoranthene	2.3
Dibenz(a,h)anthracene	4.2
Indeno(1,2,3-cd)pyrene	0.2
PCBs	
Aroclor-1242	1
Aroclor-1248	1
Aroclor-1254	1
Aroclor-1260	1
Aroclor-1262	1
Aroclor-1268	1
Total PCBs (Aroclors)	1
Total PCBs (Congeners)	1
Pesticides	
Aldrin	0.2
alpha-Chlordane	1
Dieldrin	0.2
gamma-Chlordane	1
Heptachlor	0.7
Heptachlor epoxide	0.3
Metals	
Antimony	450
Arsenic	19
Cadmium	78
Copper	45,000
Lead	800
Manganese	5,900
Mercury	65
Vanadium	1,100

DATA NOTES:

UNITS = MILLIGRAMS PER KILOGRAM

[] = DUPLICATE SAMPLE

PCBS = POLYCHLORINATED BIPHENYLS

SVOCs = SEMI-VOLATILE ORGANIC COMPOUNDS

VOCs = VOLATILE ORGANIC COMPOUNDS

NA = NOT ANALYZED

D = CONCENTRATIONS IDENTIFIED FROM ANALYSIS OF THE SAMPLE AT A SECONDARY DILUTION.

E = THE COMPOUND WAS QUANTIFIED ABOVE THE CALIBRATION RANGE.

J = THE COMPOUND WAS POSITIVELY IDENTIFIED; HOWEVER, THE ASSOCIATED NUMERICAL VALUE IS AN ESTIMATED CONCENTRATION ONLY.

JN = THE ANALYSIS INDICATES THE PRESENCE OF A COMPOUND FOR WHICH THERE IS PRESUMPTIVE EVIDENCE TO MAKE A TENTATIVE IDENTIFICATION, THE ASSOCIATED NUMERICAL VALUE IS AN ESTIMATED CONCENTRATION ONLY.

U = THE COMPOUND WAS ANALYZED FOR BUT NOT DETECTED, THE ASSOCIATED VALUE IS THE COMPOUND QUANTIFICATION LIMIT.

RX = THE SAMPLE RESULTS ARE REJECTED DUE TO MATRIX INTERFERENCE.

- NOTES:**
- ANALYTICAL RESULTS GIVEN IN MILLIGRAMS PER KILOGRAM FOR SOIL SAMPLES WITH DETECTED CONCENTRATIONS GREATER NEW JERSEY NONRESIDENTIAL SOIL REMEDIATION STANDARDS (DATED OCTOBER 2011).
 - THE EDGE OF LANDFILLED WASTES OBSERVED DURING TEST PIT ACTIVITIES IS DRAWN BASED ON OBSERVATIONS OF MATERIALS EXCAVATED DURING TEST PIT ACTIVITIES CONDUCTED FROM JULY 26, 2007 TO SEPTEMBER 6, 2007 AND MARCH 26, 2008.
 - THE PORTION OF THE GREAT SWAMP NATIONAL WILDLIFE REFUGE (GSNWR) PROPERTY BOUNDARY ON THIS FIGURE WITHIN CHATHAM TOWNSHIP, NJ WAS OBTAINED FROM CHATHAM TOWNSHIP TAX PARCEL DATA PROVIDED BY CIVIL SOLUTIONS. THE PORTION OF THE GSNWR PROPERTY BOUNDARY ON THIS FIGURE OUTSIDE OF CHATHAM TOWNSHIP IS APPROXIMATE AND WAS OBTAINED FROM THE UNITED STATES FISH AND WILDLIFE SERVICE (GEOGRAPHIC INFORMATION SYSTEMS AND SPATIAL DATA).
 - BLOCK 48-20, LOTS 184 AND 189 ARE OWNED BY ROBERT J. MIELE AS TRUSTEE FOR THE TRUST CREATED BY THE LAST WILL AND TESTAMENT OF ANGELO J. MIELE. BLOCK 48-20, LOT 189.01 IS OWNED BY THE GREEN VILLAGE FIRE DEPARTMENT.
 - THE EXTENT OF AREAS WHERE SURFACE WATER FLOW DOES NOT EXHIBIT TYPICAL BED AND BANK MORPHOLOGY IS BASED ON FIELD OBSERVATIONS MADE THROUGHOUT THE PERIOD OF INVESTIGATIVE ACTIVITIES. THE EXTENT OF THE AREA SHOWN IS APPROXIMATE.
 - ONLY SOIL ANALYTICAL RESULTS GREATER THAN NEW JERSEY NON-RESIDENTIAL SOIL REMEDIATION STANDARDS ARE POSTED.

SOURCES:

- BASEMAP FROM JAMES M. STEWART INC., LAND SURVEYORS, PHILADELPHIA, PA., (ELECTRONIC FILE: 292406.DWG DATED: 6/30/06)
- TAX PARCEL DATA FOR CHATHAM TOWNSHIP WAS PROVIDED BY CIVIL SOLUTIONS.

**ROLLING KNOLLS LANDFILL SUPERFUND SITE
CHATHAM, NEW JERSEY
DATA GAPS SAMPLING AND ANALYSIS PLAN**

PROPOSED SAMPLE LOCATIONS - SOUTH

ARCADIS

FIGURE 3b

CITY: GRANBURY, NJ; DIV: ENV; CAD: DB; TFAUTO: PLOTTED; LVR: ON; OFF: REF; PAGES: 12/19/2014 10:37 AM; ACADVER: 8.15 (LMS TECH); PROJECTNAME: ROLLING KNOLLS LANDFILL SUPERFUND SITE; LAYOUT: 3B; SAVER: 12/19/2014 11:39 AM; BY: MEYER, JULIE